

**SURVEY &
REMONUMENTATION**

OCT 07 1993

COMMISSION

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ionia</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>5W</u>	<u>I-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Oliver M. DeBruin
 REGISTER OF DEEDS

93 SEP 21 P 3:23

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marinus Mulder, in a field survey on June 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This original closing corner was set by U.S. Deputy Surveyor, Orange Risdon between May 18th and July 30 of 1831, 27 links East of standard corner. D.C. Crawford former Ionia County Surveyor performed a sectional survey in Section 3 on March 5 & 6 of 1890 Survey No. 26 recorded in Volume 2, page 106 stating he set a stone. Crawford also has witnesses on a copy of the G.L.O. notes stating: 1890 (1) 3" Black Walnut N 52 1/4° W 47 links. (2) 12" Sugar S 18°30' E 67 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe 24" long removed pipe and excavated large area to a depth of 30". Found no stone. Accepted this pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" steel rod with a 2 3/4" cap stating "Ionia County P.S. 25863", in place of pipe.

Witness:

- Nail & tag West side 22" Ash N 3° E 40.61'
- Nail & tag South side 15" Elm N 54° W 54.42'
- Nail & tag West side 22" Black Oak N 61° E 49.28'
- Nail & tag East side 15" Walnut S 18° E 24.93'

Signed by *Marinus Mulder*

Date August 30, 1993

Surveyor's Michigan License No. 25863

Filed 10/11/93