

SURVEY & REMONUMENTATION

SEP 07 1999

REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ionia</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>5W</u>	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James M. Mulder
 REGISTER OF DEEDS

93 SEP 21 P 3:23

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on June 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Orange Risdon between May 18th and July 30th of 1831. Set wood post (1) 14" Maple S39°E 11 Links (2) 30" White Oak N 50° W 50 Links PERPETUATION: D.C. Crawford former Ionia County Surveyor has marginal witness notes on a copy of the G.L.O. notes in a county survey volume stating 1891 (1) 16" Black Walnut S 12° E 74½ links (2) 10" Black Walnut N 62° W 85½ links.

This corner was found & perpetuated again by the Ionia County Road Commission during reconstruction of Kimball Road circa 1961. An iron was set with the following witness: (1) 30" Walnut N.W. 54.45' (2) 24" Hickory S.W. 74.48 feet (3) 30" Maple S.E. 88.85 feet (4) 24" Maple S.W. 47.00 feet. Professional Surveyor, James Porter # 19003 recorded this corner in Liber 2 page 14, April 21, 1978. After Porter's recording Ionia County Road Commission in 1990 during road improvements set a monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument box and 3/4" iron 12" below surface. Did not find 2 1/4" clay cylinder. Accepted this as a careful and faithful perpetuation of the position of original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 30" long fiberglass monument with a 4" brass cap stating "Ionia County Survey Monument" in place of iron in monument box.

Witnesses:

- Nail and tag Southwest side 52" Walnut N 55° W 55.00' (Crawford's 1891 witness)
- Nail and tag Northwest side 22" Maple S 60° W 46.75'
- Nail and tag 26" Maple S 30° W 46.85'
- Nail and tag power pole S 20° E 61.17'

Signed by *mad mulder* Date August 31, 1993

Surveyor's Michigan License No. 25863