

REMONUMENTATION CORNER

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia (County) Located In: Corner Code #J-7

1. Public Land Survey T 7N R 5W _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 SEP 21 P 3:24
 REGISTER OF DEEDS
 David M. DeLuca

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marinus Mulder, in a field survey on June 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 This corner was first set by U.S. Deputy Surveyor, Orange Risdon between May 18th and July 30th of 1831. Set wood post witnessed by (1) 14" Lynn S 18° W 25 links (2) 8" Beech N 8° E 8 links. Perpetuation: D.C. Crawford former Ionia County Surveyor remonumented this corner in 1891. In a copy of the G.L.O. notes found in a Ionia County Surveyors Volume he shows a marginal note but has no witnesses.

James Porter P.S. # 19003 first recorded this corner in Liber 2, page 12, April 20, 1978. Setting 1/2" rod by single proportionate measurement. Porter recorded this corner again on Feb. 17, 1981 Liber 2, page 112. He found Crawford's clay cylinder and set 1/2" bar & cap next to it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Porter's 1/2" rod and 2 1/4" clay cylinder. Accepted as a careful and faithful perpetuator of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 R. moved 1/2" rod and set 3/4" x 36" steel bar with a 2 3/4" diameter cap stating "Ionia County P.S. 25863"

Witnesses:
 Nail & tag West side 18" Basswood N 05° W 31.69'
 Nail & tag South side 22" Oak N 85° E 49.15'
 Nail & tag West side 6" Popular S 05° E 26.33'
 Centerline Kimball Highway South 49'±

LIBER 003 PAGE 30

Signed by Marinus Mulder Date August 31, 1993

Surveyor's Michigan License No. 25863