

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>7</u> N. <u>5</u> R. <u>5</u> E. <u>W.</u>		<u>G13</u>
2. PROPERTY CONTROLLING IN SECTION <u>33</u> , T. <u>7</u> N. <u>5</u> R. <u>5</u> E. <u>W.</u>		<u>9, 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. _____ R. _____ E. <u>W.</u>		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gary C. Bilow, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 30, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1891 Restoration by County Surveyor:

G13 - Set Fire Clay Monument

- 15" Oak, N35°E, 17 l.
- 15" Oak, N62°W, 64 l.
- 8" Oak, N10°W, 50-1/2 l.
- 16" Elm, N48°W, 60 l.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G13 - Found fire clay monument with 1/2" iron along SE side.  
 Found evidence of all but closest witness tree.  
 Accepted clay monument as corner.

- 9 - Set midway on line between E1/4 corner monument and computed center of section.
- 16 - Set midway on line between S1/4 corner and SE section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G13-Left clay monument with iron alongside	9-Set 3/4" x 30" capped pipe	16-Set 3/4" x 30" capped pipe
N4°W, 34.33', nail & tag in 28" Oak	N66°W, 74.17', nail & flasher in fence corner post	S19°E, 6.2', fence corner post, concrete filled iron pipe
S79°W, 76.43', nail & tag in Elm clump	S51°W, 28.00', nail & flasher in 15" Walnut	N64°E, 38.33', nail & tag in 15" Walnut
S76°E, 123.72', nail & tag in 34" Oak	N30°E, 35.40', 3" angle iron fence corner post	N21°W, 34.55', nail & tag in 13" Walnut
S10°W, 17.26', nail & tag in 2" twin Hickory	S16°W, 26.2', top center of marker for underground telephone cable	N52°W, 39.75', nail & tag in 13" Oak

SIGNED BY \_\_\_\_\_ SURVEYOR'S MICHIGAN REGISTRATION NO. 26453 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 APPROVED AND SIGNED BY Bilow CHIEF OF SURVEY PARTY DATE \_\_\_\_\_  
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 26453