

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ionia</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>6W</u>	<u>B-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Diane M. Adams
 REGISTER OF DEEDS

93 DEC 27 P 1:07

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on September 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by G.L.O. Deputy Surveyor, Orange Risdon. He set a wood post witnessed by, 12" White Oak S 38° W 37 links, 16" White Oak N 34° E 33 links. There is no record of perpetuation of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ESTABLISHED this corner on line between the Southeast and Southwest corners of Section 7 and on a fence line running North and South & is accepted as a careful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 3/4" x 36" steel bar with a 2 3/4" diameter cap stamped "Ionia County P.S. 25863" witnessed by:

- Nail & tag East side 16" Twin Cherry N 15" W 6.79 feet
- Nail & tag North side 12" Mulberry S 78° W 14.75 feet
- Nail & tag West side 30" Oak S 14° W 26.15 feet
- Nail & tag Northwest side 5" Elm S 45° W 18.18 feet

Signed by *Marinus Mulder* Date October 21, 1993

Surveyor's Michigan License No. 25863