

SURVEY & REMONUMENTATION

FEB 16 1994

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>7N</u> R <u>6W</u> | <u>G-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 DEC 27 P 1:07
Oliver J. Adams
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marinus Mulder, in a field survey on October 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Orange Risdon in 1831. A wood post was set witnessed by a 14" White Oak S 43° E 9 links and a 14" Lynn N 32° W 67 links.
 PERPETUATION: A.C. Smith former Ionia County Surveyor performed a survey in this area August 10, 1876 found in Volume 1 page 184 of the Ionia County Surveyors records. Smith says the 1/4 corners were set but showed no witnesses of what was set for corner. In January 11-13, 1888 D.C. Crawford former Ionia County Surveyor performed a survey in Section 28 found in Volume 1 page 478 of the Ionia County Surveyors records. Crawford shows the East 1/4 corner but shows no witnesses or what was set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The position of this corner falls in a quarter section line gravel road. The road was excavated with a backhoe opposite a fence running South. At a depth of 18 inches found a large pointed stone with smaller stones around it. Accepted this as the position of G-10. Set a 3/4" x 24" steel rod & cap next to the stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel rod with a 2 3/4" cap stamped "Ionia County P.S. 25863" witnessed by:
 Nail & tag West side 3" Crabapple S 01° E 25.95'
 Nail & tag West side power pole N 4° E 211.07'
 Corner of Southwest leg of high power tension tower S 42° E 80.72'
 Corner of Northwest leg of high power tension tower S 51° E 70.78'

Signed by *Marinus Mulder* Date October 28, 1993
 Surveyor's Michigan License No. 25863