

SURVEY & REMONUMENTATION COMMISSION
 APR 10 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in IONIA
 (County)

Located in: _____ Corner Code # _____
 1. Public Land Survey T 7N R 6W _____ H-10
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____
 in Section S _____ T _____
 3. Miscellaneous S _____ T _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 94 DEC 29 P 1 58
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on OCTOBER 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 THIS CORNER WAS NOT ESTABLISHED BY U.S. GOVERNMENT SURVEYORS.
 THERE IS NO RECORD OF ESTABLISHMENT BY THE IONIA COUNTY SURVEYORS OFFICE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 EXCAVATED ROAD AT T INTERSECTION AND FOUND BRICK AND CROCKERY.
 ACCEPTED THIS AS EVIDENCE AND HELD AS THE POSITION OF THE SECTION CENTER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET A 3/4" X 24" STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED "IONIA COUNTY - P.L.S. 25863"

WITNESSED BY:
 NAIL & TAG EAST SIDE 24" WALNUT S 33° W 64.22'
 NAIL & TAG WEST SIDE 26" OAK N 30° E 70.82'
 SOUTHWEST CORNER HOUSE N 70° E 104.62'
 CENTERLINE OF ROAD SIGN POST N 50° W 39.01'

Ratified by Peer Group
 P.A. 345 Ionia County

Date 12-22-94
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder

Date 12-27-94

Surveyor's Michigan License No. 25863