

SURVEY & REMONUMENTATION
APR 10 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in IONIA Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 7N R 6W I-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORDING
 94 DEC 29 P 1:59
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, MARINUS MULDER, in a field survey on SEPTEMBER 9 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR ORANGE RISDON IN 1831. A WOOD POST WAS SET BUT NO WITNESSES WERE RECORDED.
 PERPETUATION: D.C. CRAWFORD FORMER IONIA COUNTY SURVEYOR PERFORMED A SECTIONAL SURVEY OF SECTION 35, MARCH 3 AND 4TH 1890 RECORDED IN VOLUME 2 PAGE 102 OF THE IONIA COUNTY SURVEYORS RECORDS. CRAWFORD DID NOT SHOW WHAT WAS SET OR FOUND FOR I-11.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 EXCAVATED ROAD AND FOUND LARGE CUT STONE 8" BELOW ROAD SURFACE. ACCEPTED THE CUT STONE AS THE PERPETUATED CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET A 3/4" X 24" STEEL BAR WITH A 2 3/4" DIAMETER CAP STAMPED "IONIA COUNTY - P.L.S. 25863"
 WITNESSED BY:
 NAIL & TAG WEST SIDE 10" CHERRY NORTH 39.75'
 NAIL & TAG NORTH SIDE 16" ELM S 52° E 54.24'
 NORTHEAST CORNER OF STONE ON MAIN HOUSE FOUNDATION S 60° W 144.80'
 NAIL & TAG WEST SIDE 12" BASSWOOD S 04° E 116.67'

Ratified by Peer Group
 P.A. 345 Ionia County

Date 12-22-94
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 12-27-94
 Surveyor's Michigan License No. 25863