

SURVEY & REMONUMENTATION

1993

REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia Located In: Corner Code #
(County)

1. Public Land Survey T 7N R 6W L-1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 DEC -7 P 3:40
 Diana M. Adams
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on October 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 This North 1/4 closing corner was not set by the Government Surveyors.
 Historical Establishment and/or Perpetuation: D.C. Crawford former Ionia County Surveyor performed a sectional survey in Section 1, April 19, 1892. Crawford said he set a stone & brick. This survey is found in Volume 2 page 262 of the County Surveyors Records. Crawford shows marginal witness notes to this corner found in the County Surveyors copy of the G.L.O. notes. He states: 1906, 24" White Oak N 45° W 77 1/2 links and 36" Black Oak S 5° E 48 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 The 24" White Oak which Crawford called for in 1906 is still standing. The witness distance was intersected with the section line and we excavated. A large stone was found about 5" below the gravel surface and around the stone brick was found at a depth of 9". This was accepted as the corner and a 3/4" rod and cap was placed on the Easterly side.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 3/4" x 36" steel rod with a 2 3/4" diameter cap stamped "Ionia County - P.S. 25863"
 Witnessed by:
 Nail & tag East side 10" Twin Walnut N 38° E 42.92'
 Nail & tag West side 6" Elm N 2° W 35.32'
 Nail & tag Southwest side 40" White Oak N 50° W 52.18' (Crawford's 1906 witness)
 Nail & tag Northwest side 18" Oak S 71° W 55.56'
 Centerline of road approximately 8' North

Signed by _____ Date October 28, 1993
 Surveyor's Michigan License No. 25863