

LAND CORNER RECORDATION CERTIFICATE LIBER 4 PAGE 106  
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in IONIA Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T7 N R8 W C-6  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 IONIA COUNTY  
 RECEIVED FOR RECORD  
 23 NOV 99 3:04 P.M.  
 DIANE M. ADAMS  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

I, MARINUS MULDER, in a field survey on JUNE 17 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR NOAH BROOKFIELD IN 1837. A WOOD POST WAS SET WITNESSED BY A 12" WHITE OAK SOUTH 44 LINKS AND A 18" WHITE OAK N 56° W 45 LINKS.

PERPETUATION: THERE ARE NO RECORDED COUNTY SURVEYS FOR C-6.

THE IONIA COUNTY ROAD COMMISSION IMPROVED WHITES BRIDGE ROAD IN 1962  
 PROFESSIONAL SURVEYOR GORDON NEDERVELD NO. 21272 RECORDED C-6 AUGUST 12, 1976 FOUND IN LIBER 1, PAGE 204 OF ACT 74 RECORDS. NEDERVELD FOUND A P.K. NAIL ON CENTERLINE IN LINE WITH A FENCE TO THE EAST, WITNESSED BY: IRON EAST 33 FEET; P.K. NAIL IN N.E. SIDE POWER POLE S.E. 47.06 FEET; SPIKE 8" OAK E.N.E. 60.29 FEET; P.K. NAIL IN SIGN POST W.N.W. 35.97 FEET.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 4" BELOW THE PAVED ROAD SURFACE AND OPPOSITE A FENCE LINE EAST AND WEST FOUND A 3/4" x 12" BOAT SPIKE. BELOW BOAT SPIKE FOUND A 1/2" X 17" ROD NO FURTHER EVIDENCE WAS FOUND.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 REPLACED THE EXISTING MONUMENTATION WITH A 7/8" x 30" STEEL BAR WITH A 4" DIAMETER CAP STAMPED "IONIA COUNTY SURVEY MONUMENT -P.S. 25863" SET IN A MONUMENT BOX WITNESSED BY:

- N&T SOUTH SIDE 8" POPLAR S 75° W 28.30'
- N&T SOUTH SIDE 6" POPLAR N 80° W 29.85'
- N&T SOUTH SIDE 24" OAK EAST 43.13'
- N&T EAST SIDE 10" ELM N 15° W 84.97'

Signed by Marinus A. Mulder Date 11-3-99  
 Surveyor's Michigan License No. 25863

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN. 1983  
 ADAPTED FOR WORD PROCESSING MARCH, 1993

Ratified by Peer Group  
 P.A. 345 Ionia County

Date August 18, 1999  
 Marinus A. Mulder, Chairman

