

DEC 17 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 195

For corners in IONIA (County)

Located In: Corner Code #

- 1. Public Land Survey T 7N R 8W F-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

STATE OF MICHIGAN IONIA COUNTY RECEIVED FOR RECORD

10 OCT 95 4:05 P.M.

DIANE K. ADAMS REGISTER OF DEEDS Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13 containing numbers 1-36.

I, MARINUS MULDER, in a field survey on April 3 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first established by U.S. Deputy Surveyor, Noah Brookfield in 1837. A wood post was set witnessed by a 12" White Oak N 33° E 44 links and a 12" White Oak N 48° W 52 links. There is no written record of Perpetuation of this corner by the County Surveyor. The Ionia County Road Commission has witnesses for F-9 in its County Index Maps. The map calls for a boatspike over a stone, witnessed by: 14" Oak N.W. 34.70 feet; 4" Maple S.E. 30.75 feet; 14" Apple S.E.40 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod and cap set by Medema & VanKooten No. 08618, and a boat spike over a stone with smaller stones at its base, 12" deep in centerline of Pinkney Road and opposite fence lines East and West. Accepted the stone as the correct corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 3/4" x 24" rod with a 2 3/4" diameter cap stamped "Ionia County, P.S. 25863" in place of the 1/2" rod and cap witnessed by:

- 1/2" rod and cap West 33.00 feet (No.08618)
Nail & tag North side 40" Maple S 76° E 30.10 feet
Nail & tag Southwest side 22" Hickory N 33° W 68.79 feet
Nail & tag Northeast side 2"-4" Maple clump S 22° E 67.12 feet

Witnessed by Elev Group P.A. 343 Ionia County

Date 9-27-95 Marinus A. Mulder, Chairman

Signed by [Signature] Date 9-30-95

Surveyor's Michigan License No. 25863

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN.