

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 003 PAGE 224

For corners in IONIA Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 7 N R 8 W G-3
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

16 NOV 95 4:21 P.M.

DIANE M. ADAMS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARINUS MULDER, in a field survey on AUGUST 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR NOAH BROOKFIELD IN 1837. A WOOD POST WAS SET WITNESSED BY A 10" BEECH S 49° W 10 LINKS AND A 14" BEECH N 52° E 28 LINKS.
PERPETUATION: THOMAS CORNELL FORMER IONIA COUNTY SURVEYOR PERFORMED A SURVEY OF SECTION 4 NOVEMBER 15-20, 1877 RECORDED IN LIBER 1, PAGE 256 OF THE IONIA COUNTY SURVEYORS RECORDS. CORNELL STATES HE SET A STONE WITNESSED BY A 14" PEPPERIDGE N 29° 30' E 144 LINKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 AT THE INTERSECTION OF THE REMAINS OF FENCE LINES RUNNING NORTH-SOUTH AND WEST, FOUND 2 LARGE STONES OVER SMALLER STONES. ACCEPTED THE STONES AS THE POSITION OF G-3.
 DISTANCE G-3 TO G-2 = 2635.97 FEET
 DISTANCE G-3 TO F-3 = 2659.00 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET A 3/4" X 24" STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED "IONIA COUNTY 25863" IN CENTER OF 2 STONES WITNESSED BY:
 NAIL & TAG SOUTH SIDE 30" OAK N 83° W 13.75 FEET
 NAIL & TAG EAST SIDE 14" BASSWOOD N 52° W 5.97 FEET
 NAIL & TAG WEST SIDE 10" BEECH N 4° E 12.91 FEET
 NAIL & TAG EAST SIDE 18" CHERRY CLUMP S 15° E 9.42 FEET

Ratified by Peer Group
 P.A. 345 Ionia County

Date Nov. 1, 1995
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 11-14-95
 Surveyor's Michigan License No. 25863