

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in IONIA Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 7N R 8W _____ J-3
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORD

10 OCT 95 4:06 P.M.

DIANE M. ADAMS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on March 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first established by U.S. Deputy Surveyor, Noah Brookfield in 1837. A wood post was set witnessed by a 18" White Oak N 34° 53 links and a 12" Red Oak S 75° W 34 links.

Perpetuation: There are no county surveys recorded for Section 11, however, A.C. Smith former Ionia County Surveyor performed a sectional survey in Section 2 T7N-R8W, October 9, 1876, recorded in Volume 1, page 200 of County Survey Records. Smith does not show what was set or found for J-3.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Excavated road at T intersection of Andre & Ellison Roads opposite an occupation fence to the West with a back hoe. At a depth of 8" found a 8" x 14" stone with broken crockery at the stone's base. Accepted the stone as the corner and set a 3/4" diameter x 24" long steel rod on the West side of the stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 3/4" diameter x 24" long steel rod with a 2 3/4" diameter cap, stamped "Ionia County P.S. 25863" witnessed by:

- Centerline Road sign post N 60° E 35.87 feet
- Nail & tag North side 8" Walnut N 75° W 21.65 feet
- Nail & tag South side railroad tie post S 60° W 25.02 feet
- Nail & tag power pole S 37° E 109.30 feet

Ratified by Peer Group
P.A. 345 Ionia County

Date 9-27-95
Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder

Date OCTOBER 2, 1995

Surveyor's Michigan License No. 25863