

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 198

For corners in
IONIA
 (County)

Located In: Corner Code #

1. Public Land Survey T 7N R 8W J-4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

10 OCT 95 4:06 P.M.

DIANE M. ADAMS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on March 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

The center of section was not set by the U.S. Government Surveyors. There is no documentation of this corner being set by the County Surveyors or any other surveyor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Excavated road bed at T intersection but found no evidence. This corner was established by intersecting the North-South and East-West 1/4 lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A 3/4" x 24" steel bar with a plastic 2 3/4" diameter cap was set for J-4 witnessed by:
 Nail & tag Northwest side power pole S 34° W 23.49 feet
 Nail & tag Southwest side 10" Elm N 30° W 60.02 feet
 Nail & tag Northeast side 5" wood post N 47° W 69.40 feet
 Northwest corner house S 6° E 81.86 feet

Ratified by Peer Group
 P.A. 345 Ionia County

Date 9-27-95
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date OCTOBER 2, 1995

Surveyor's Michigan License No. 25963