

REMONUMENTATION

DEC 02 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 346

For corners in IONIA Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T7 N R8 W K-2 _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
IONIA COUNTY
RECEIVED FOR RECORD
12 NOV 97 3:46 P.M.
DIANE H. ADAMS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on SEPTEMBER 18 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR NOAH BROOKFIELD IN 1837. A 12" ELM WAS CALLED FOR AS K-2. NO WITNESSES GIVEN.

PERPETUATION: A.C. SMITH FORMER COUNTY SURVEYOR PERFORMED A SURVEY OF SECTION 1, T7N-R8W, JUNE 1875, RECORDED IN VOLUME 1, PAGE 118 OF IONIA COUNTY SURVEY RECORDS. SMITH NOTED THAT A STAKE MARKED THE POSITION OF K-2.

THE IONIA COUNTY ROAD COMMISSION IMPROVED HAWLEY HIGHWAY IN 1959.

THE ROAD COMMISSION HAS NO WITNESSES FOR K-2.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
EXCAVATED HAWLEY HIGHWAY AT CENTERLINE OF ROAD OPPOSITE A FENCE LINE WEST, BUT FOUND NO EVIDENCE.

ESTABLISHED K-2 ON LINE BETWEEN K-1 AND K-3 AND OPPOSITE A FENCE LINE RUNNING WEST. THIS POSITION IS 6.5 FEET WEST OF THE ROAD CENTERLINE. EXCAVATED TO A DEPTH OF 40" BUT FOUND NO EVIDENCE OF A CORNER. DISTANCE SOUTH TO K-3 MEASURES 2647.70 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET A 24" MONUMENT WITH A 4" DIAMETER CAP STAMPED "IONIA COUNTY-25863" WITNESSED BY:

- NAIL & TAG SOUTH SIDE WOOD POST WEST 15.20 FEET
- NAIL & TAG WEST SIDE 2" ASH N26°E 69.67 FEET
- NAIL & TAG EAST SIDE 4" ELM N47°W 18.22 FEET
- EAST EDGE STEEL FENCE POST S50°W 30.48 FEET
- CENTERLINE HAWLEY HIGHWAY EAST 6.5 FEET

Signed by Marinus A. Mulder

Date 11-12-97

Surveyor's Michigan License No. 25863

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993



Ratified by Deer Group
P.A. 346 Ionia County

Date 10-20-97
Marinus A. Mulder, Chairman