

DEC 0 2 1897

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 348

For corners in IONIA Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T7 N R8 W K-4 \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
IONIA COUNTY  
RECEIVED FOR RECORD

12 NOV 97 3:51 P.M.

DIANE M. ADAMS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on SEPTEMBER 17 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR NOAH BROOKFIELD IN 1837. A WOOD POST WAS SET WITNESSED BY A 10" BEECH S70°W 8 LINKS AND A 10" BEECH S70°E 19 LINKS.

THERE IS NO RECORDED INFORMATION IN THE COUNTY SURVEYORS RECORDS FOR K-4.

THE IONIA COUNTY ROAD COMMISSION IMPROVED HAWLEY HIGHWAY IN 1959. THE COUNTY ROAD COMMISSION WITNESSES FOR K-4 FOUND ON THE SECTION CORNER INDEX MAP IS: 6" MAPLE N.E. 68.90 FEET; 26" OAK S.W. 107.60 FEET; 15" ELM S.W. 48.00 FEET

PROFESSIONAL SURVEYOR THOMAS CHETTLEBURGH NO. 16036, RECORDED K-4 APRIL 1986, FOUND IN LIBER 2, PAGE 260 OF ACT 74 RECORDS. CHETTLEBURGH FOUND A SPIKE WHICH CHECKED WITH THE IONIA COUNTY ROAD COMMISSION WITNESSES AND LEFT IN PLACE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
AT THE INTERSECTION OF HAWLEY HIGHWAY AND SCOTT ROAD, FOUND A 1/2" ROD AT THE ROAD SURFACE. THE 26" OAK WITNESS TREE SOUTHWEST CALLED FOR BY THE ROAD COMMISSION STILL EXISTS AS A 60" STUMP. EXCAVATED BELOW 1/2" ROD AND AT A DEPTH OF 30" FOUND A GROUP OF SMALL STONES. EXCAVATED BELOW STONE CAIRN, BUT FOUND NO OTHER EVIDENCE. ACCEPTED THIS MONUMENTATION AS THE PERPETUATED CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET A 24" MONUMENT WITH A 4" DIAMETER CAP STAMPED "IONIA COUNTY-25863" IN PLACE OF THE EXISTING MONUMENTATION WITNESSED BY:

- NAIL & TAG SOUTH SIDE 28" MAPLE S65°E 35.72 FEET
- NAIL & TAG SOUTH SIDE 24" MAPLE S24°E 51.92 FEET
- NAIL & TAG WEST SIDE 38" MAPLE S31°E 66.60 FEET
- NAIL & TAG TOP CENTERLINE 60" OAK STUMP S5°W 108.72 FEET

Signed by Marinus A. Mulder  
Surveyor's Michigan License No. 25863

Date 11-12-97

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971

REVISED MAY 14, 1976  
REVISED JAN. 1983  
ADAPTED FOR WORD PROCESSING MARCH 1997



Notified by Map Group  
P.A. 348 Ionia County

Date 10-20-97  
Marinus A. Mulder, Chairman