

**SURVEY &
REMONUMENTATION**

FEB 18 1994

REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ionia</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>7W</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 DEC 27 P 1:13
 REGISTER OF DEEDS
Devin M. O'Brien

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on September 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Orange Risdon. A wood post was set 36 links North of the standard corner witnessed by a 12" Beech S 45° E 26 links and a 12" Beech N 49° E 38 links. Risdon set this in 1831.

PERPETUATION: D.C. Crawford former Ionia County Surveyor performed a survey in the NW 1/4 of Section 30 August 11, of 1887 which is recorded in Volume 1 page 402 of the County Surveyors records. Crawford noted that the old witnesses from the G.L.O. were still standing but he did not take new witness measurements. Crawford also did not state what he set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

An excavation was made at the proper jog distance North of the standard corner for T7N-R8W. There is fence running North and South but no fence running to the East. A large pointed stone with smaller stones at its base was found about 6" below the surface. This was accepted as the corner and a 3/4" x 24" steel rod and cap was placed next to it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" steel rod with a 2 3/4" cap stamped "Ionia County P.S. 25863" witnessed by:
 Nail & tag East side 10" Maple S 17° E 12.00'
 Nail & tag West side 8" Ash N 40° E 14.75'
 Nail & tag Southwest side 10" Elm N 31° E 28.88'
 Nail & tag Southeast side 18" Maple N 35° W 34.52'
 Northeast corner of Section 25, T7N-R8W South 23.57'

Signed by *Marinus Mulder* Date 10-19-93
 Surveyor's Michigan License No. 25863