

**SURVEY & REMONUMENTATION**  
**APR 10 1995**  
**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in IONIA Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 7N R 7W B-10  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 IONIA COUNTY  
 RECEIVED FOR RECORDS  
 94 DEC 29 P1:58  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

I, MARINUS MULDER, in a field survey on APRIL 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 THIS CENTER OF THE SECTION WAS NOT SET BY THE G.L.O.

ESTABLISHMENT: D.C. CRAWFORD FORMER IONIA COUNTY SURVEYOR ESTABLISHED THE CENTER WHILE DOING A SECTIONAL SURVEY IN SECTION 30, AUGUST 11, 1887. CRAWFORD DID NOT STATE WHAT HE SET BUT HAS WITNESSES AS FOLLOWS: 24" MAPLE N 5° E 34 1/2 LINKS AND 12" MAPLE N 50° E 57 3/4 LINKS. THIS SURVEY IS RECORDED IN VOLUME 1 PAGE 402 OF THE COUNTY SURVEYORS NOTES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AREA WHERE THE NORTH-SOUTH AND EAST-WEST 1/4 LINE FENCES MEET. BOTH FENCES ARE IN BAD SHAPE AND NO ANCHOR POST IS STANDING. BITS AND PIECES OF WOOD POST AND WIRE WAS FOUND IN THE VICINITY AND A SEARCH BY SHOVELS PROCEEDED. A LARGE POINTED STONE ON END WAS FOUND NEAR THE FENCE REMAINS. NO 1887 BEARING TREES REMAIN. THE DISTANCE MEASURED TO THE WEST 1/4 CORNER IS REASONABLE. CRAWFORD'S DISTANCE BEING 2670.36 FEET AND OURS BEING 2674.31 FEET. I ACCEPTED STONE AS THE CENTER AND SET A 3/4" BAR AND CAP NEXT TO IT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 SET 3/4" X 24" STEEL BAR WITH A 2 3/4" DIAMETER CAP STAMPED "P.S. 25863"

WITNESSED BY:

- NAIL & TAG NORTH SIDE 12" OAK N 47° W 24.55'
- NAIL & TAG SOUTHEAST SIDE 8" OAK S 17° W 8.88'
- NAIL & TAG EAST SIDE 6" WALNUT S 53° W 18.31'
- NAIL & TAG NORTHEAST SIDE 12" OAK N 11° E 8.34'

Rectified by Peer Group  
 P.A. 345 Ionia County

Date 4-20-94  
 Marinus A. Mulder, Captain

Signed by marinus a mulder Date 12-27-94  
 Surveyor's Michigan License No. 25863