

FEB 18 1994


REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

<u>Ionia</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>7N</u> R <u>7W</u>	<u>B-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		


 REGISTER OF DEEDS
 93 DEC 27 P 1:05
 STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marinus Mulder, in a field survey on September 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 This corner was first set by U.S. Deputy Surveyor, Orange Risdon. . A wood post was set witnessed by a 12" Elm S 47° W 31 links and a 8" Beech N 67° E 36 links. This was set in 1831.

PERPETUATION: D.C. Crawford former Ionia County Surveyor performed a survey in the NW 1/4 of Section 30 August 11, 1887, which is recorded in Volume 1 page 402 of the County Surveyors records. Crawford makes no mention of B-11, but shows that he did set the section center.

Richard Crater, Professional Surveyor #16924 recorded this corner October 23, 1986 found in Liber 2 page 263. Crater called for a corner post at the intersection of fences.

Tom Chettleburgh, Professional Surveyor #16036 also did some work in this section and a 3/4" (see back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 We made a thorough search of the area and also had field measurements to adjacent section corners. No historical evidence from the 1800's was found. Accepted the position of Chettleburgh's iron and replaced this with a 3/4" x 36" steel rod.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set a 3/4" x 36" steel rod with a 2 3/4" cap stamped "Ionia County P.S. 25863" Witnessed by:

- Nail & tag South side 12" Maple North 7.50'
- Nail & tag North side 8" Maple N 55° E 18.22'
- Nail & tag West side 14" Ash N 60° W 7.04'
- Nail & tag North side 12" Ash East 37.18'

Signed by Marinus Mulder Date 10-19-93

Surveyor's Michigan License No. 25863

B. con't.

rod and cap bearing his number was found at the position of B-11 which matched the witness distances of Crater.

~~SECRET~~