

**SURVEY &
REMONUMENTATION**

OCT 1 1 1994

REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ionia</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>7</u> N R <u>7</u> W	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 94 JUN -6 P 3:53
 REGISTER OF DEEDS
David M. DeWitt

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on October 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first established by U.S. Deputy Surveyor, Lucious Lyon in 1826. A wood post was set witnessed by a 7" Beech N 87° E 37 links and a 12" White Oak N 46° W 53 links. There is no record of County Surveyor perpetuation of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone with stones around 2 feet deep in a East-West and North-South tree line intersection. There are no remaining fences; but traces of wire were found. Accepted the stone as the corner and set a 3/4" steel bar next to it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 3/4" x 24" steel bar with a 2 3/4" diameter cap stamped "P.S. 25863" next to the stone witnessed by:

- Nail & tag West side 40" Poplar clump N 12° W 38.66'
- Nail & tag South side 14" Twin Poplar S 83° W 18.02'
- Nail & tag North side 24" Poplar clump N 73° E 3.58'
- Nail & tag 8" Poplar South 0.93'

Ratified by Peer Group
P.A. 345 Ionia County

Date 4-20-94 M.A.M.
Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 4-21-94

Surveyor's Michigan License No. 25863