

**SURVEY & REMONUMENTATION**

OCT 07 1993

COMMISSION

REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ionia  
(County)

Located In:

Corner Code ≠#

- |                                    |                         |             |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey              | T <u>8N</u> R <u>5W</u> | <u>E-13</u> |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

*Clarence M. DeWitt*  
 REGISTER OF DEEDS

93 SEP 21 P 3:24

STATE OF MICHIGAN  
 IONIA COUNTY  
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on June 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

This corner was first set by U.S. Deputy Surveyor, Robert Clark Jr. February of 1831. He set a wood post witnessed by (1) 16" White Oak N 62° E 65 links (2) 11" White Oak N 71° W 25 links Perpetuation: No recorded of perpetuation

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At road intersection excavated road bed with a backhoe and found large pointed stone with smaller stones around the base; at a depth of 24". This stone is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" steel bar with a 2 3/4" diameter cap next to stone stating "Ionia County P.S. 25863" with the following witnesses:

- Nail & tag West side 26" Oak S 32° W 27.92'
- Nail & tag East side 24" Hickory N 31° W 43.32'
- Nail & tag Northwest side 12" Oak N 66° E 70.68'
- Nail & tag South side 16" Hickory S 69° E 92.90'

003 PAGE 28

Signed by *Marinus Mulder*

Date August 30, 1993

Surveyor's Michigan License No. 25863

*filed 10/11/93*