

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 **003** PAGE **230**

For corners in IONIA Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 8 N 5 W _____ F-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 16 NOV 95 4:24 P.M.
 DIANE M. ADAMS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, MARINUS MULDER, in a field survey on AUGUST 23 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR ORANGE RISDON IN 1831. A WOOD POST WAS SET WITNESSED BY A 17" WHITE OAK N 62° E 65 LINKS AND A 13" WHITE OAK N 58° W 45 LINKS. THERE IS NO RECORDED DOCUMENTATION OF THIS CORNER BEING PERPETUATED BY THE COUNTY SURVEYOR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 EXCAVATED GRAVEL ROAD BED (NICKLEPLATE ROAD) OPPOSITE AN ESTABLISHED FENCE LINE RUNNING NORTH WITH A BACK HOE AND FOUND A LARGE PILE OF STONES. NO OTHER EVIDENCE WAS FOUND. ACCEPTED THE STONE PILE AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF F-13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET A 3/4" X 24" STEEL ROD WITH A 2 3/4" DIAMETER CAP STAMPED "IONIA COUNTY P.S. 25863" WITNESSED BY:
 NAIL & TAG SOUTH SIDE 30" OAK N 65° E 41.74 FEET
 NAIL & TAG SOUTHWEST SIDE 26" OAK N 2° W 30.64 FEET
 NAIL & TAG WEST SIDE 16" ELM S 4° E 31.08 FEET
 NAIL & TAG NORTH SIDE 12" ASH S 59° W 47.65 FEET
 NORTH 1/4 CORNER SECTION 4 (F-1) T7N-R5W, 3/4" STEEL ROD WITH A 2 3/4" DIAMETER CAP, NEXT TO STONE IS EAST 11.50 FEET

Ratified by Peer Group
 P.A. 345 Ionia County
 Date Nov. 1, 1995
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date 11-14-95

Surveyor's Michigan License No. 25863