

**SURVEY &
REMONUMENTATION**

OCT 07 1993

COMMISSION

REMONUMENTATION CORNER

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
LANSING COUNTY
REGISTER OF DEEDS
RECEIVED FOR RECORD
93 SEP 21 P 3:23

For corners in

Ionia
(County)

Located In:

Corner Code -#

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>8</u> N R <u>5</u> W | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marinus Mulder, in a field survey on June 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner was first established by U.S. Deputy Surveyor Robert Clark Jr. February of 1831. Wood post witnessed by (1) 8" White Oak N 40° W 22 links (2) 10" Sugar Maple N 13° E 13 links. No record of perpetuation exists.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod next to ancient 3" x 3" rotted wood stake. Excavated area but found no stone. Could not determine who set rod. Accepted as the best available evidence of the position of the original corner, since it agrees closely with local possession lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1/2" rod and set 3/4" x 36" steel rod with 2 3/4" diameter cap.

Witnesses:

- Nail & tag North side 15" Walnut S 48° E 35.78'
- Nail & tag West side 22" Oak N 70° E 64.57'
- Nail & tag North side 22" Ash N 29° E 43.27'
- Nail & tag South side 15" Elm N 36° W 40.61'
- Northeast corner Section 3, Lyons Township East 17.75'

LIBER 003 PAGE 2A

Signed by Marinus Mulder Date August 30, 1993

Surveyor's Michigan License No. 25863

filed 10/11/93