

SURVEY & REMONUMENTATION

OCT 07 1993

COMMISSION

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ionia</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8</u> N R <u>6</u> W	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD
 93 SEP 21 9:24
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marinus Mulder, in a field survey on July 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner first set by Orange Risdon U.S. Deputy Surveyor between November 30, 1830 to July 23, 1831. Set a post, witnessed by 16" White Oak S 19° W 10 Links; 24" White Oak N 23° E 85 links.

There were 2 county surveys performed in Section 20 of Ronald Township recorded in Volume 3 page 20 and survey No.45 recorded in Volume 2, page 186. Neither survey gives any information on this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike below Bituminous road surface. Excavated road bed but found nothing else. Although the County Road Commission shows no witnesses in their files, more than likely this was set by them. Position fits occupation line to the North. This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed spike and set a 30" long fiberglass monument with a 4" brass cap stating "Ionia County Survey Monument"

Witnesses:

- Nail & tag West side 18" Cherry North 75.26'
- Nail & tag East side 14" twin Walnut S 15° E 70.76'
- Nail & tag power pole S 45° W 70.10'
- Southwest corner garage N 40° E 124.72'

LIBER 003 PAGE 25

Signed by Marinus Mulder Date _____

Surveyor's Michigan License No. 25863

filed 10/11/93