

LAND CORNER RECORDATION CERTIFICATE LIBER 003 PAGE 202
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
IONIA
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 8N R 6W _____ F-6
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 IONIA COUNTY
 RECEIVED FOR RECORD

10 OCT 95 4:07 P.M.

DIANE M. ADAMS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on March 22 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 This corner was not established by U.S. Government Surveyors.

Establishment: D.C. Crawford former Ionia County Surveyor performed a sectional survey of Section 31 May 2 & 3, 1890 recorded in Volume 2 page 126 of the County Surveyors Records. Crawford shows the center at the intersection of the 1/4 lines but has no witnesses or shows what was set for the center.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Bill Tingley's (Professional surveyor No. 30104) 1/2" rod and cap in a stone pile at the base of a fence post with fence running East and North, and remains of fence running West & South. Accepted this as the best position of the historical center of section as set by Crawford.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 3/4" x 24" Rod with a 2 3/4" diameter cap stamped "Ionia County - P.S. 25863" in place of Tingley's rod and cap and witnessed by:

- Nail & tag South side 8" Oak N 53° W 8.27 feet
- Nail & Tag South side 8" Cherry S 83° W 18.56 feet
- Nail & Tag East side 12" Twin Oak S 13° W 14.81 feet
- Nail & tag Southwest side 8" Cherry S 55° E 5.49 feet

Ratified by Peer Group
 P.A. 345 Ionia County

Date 9-27-95
Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date OCTOBER 2, 1995

Surveyor's Michigan License No. 25863