

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in IONIA Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T8N R6W I-2
T R
T R
T R

2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
IONIA COUNTY
REGISTERED FOR RECORDS

94 NOV 22 P 3:43

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARINUS MULDER, in a field survey on JUNE 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS FIRST ESTABLISHED BY U.S. DEPUTY SURVEYOR, ORANGE RISDON IN 1832. A WOOD POST WAS SET WITNESSED BY A 18" WHITE ASH N 51° E 47 LINKS AND A 16" WHITE OAK S 51° W 20 LINKS. THERE IS NO RECORD OF ANY COUNTY SURVEYS IN SECTION 2 OR 3. THE IONIA COUNTY ROAD COMMISSION RECONSTRUCTED AND PAVED VAN VLECK ROAD IN 1962. PLAN INFORMATION IS FOUND ON SHEET NO. 11 OF STATE PROJECT CS 34-81. THE PLANS CALL FOR A BOAT SPIKE AND STONE WITNESSED BY:
30" ELM SOUTH-SOUTHEAST 30.20'
24" MAPLE S.W. 31.45'
CORNER FENCE POST NORTH-NORTHWEST 27.85'
CORNER FENCE POST SOUTH 31.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

EXCAVATED ROAD AND 2" BELOW SURFACE FOUND 1/2" ROD. REMOVED ROD AND AT A DEPTH OF 16" FOUND A 3/4" X 8" BOAT SPIKE. BELOW BOAT SPIKE AT A DEPTH OF 24" FOUND A LARGE POINTED STONE. ACCEPTED THE POSITION OF THE BOAT SPIKE AND STONE AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Ratified by Peer Group
P.A. 345 Ionia County

Date 10-20-94
Marinus A. Mulder, Chairman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED THE 1/2" ROD AND BOAT SPIKE AND SET A 24" FIBERGLASS MONUMENT WITH A 4" DIAMETER BRONZE CAP STAMPED "IONIA COUNTY SURVEY MONUMENT - DO NOT DISTURB" WITNESSED BY:
NAIL & TAG NORTH SIDE 6" CHERRY CLUMP S 58° E 75.35'
NAIL & TAG EAST SIDE 8" WOOD POST NORTH 34.7'
NAIL & TAG WEST SIDE 6" WOOD POST N 18° W 36.39'
NAIL & TAG WEST SIDE 6" ELM CLUMP S 20° W 50.65'

Signed by Marinus A. Mulder Date 11-1-94
Surveyor's Michigan License No. 25863

132 132