

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 **003** PAGE **201**

For corners in IONIA Located In:  
 Corner Code # \_\_\_\_\_  
 (County) \_\_\_\_\_

1. Public Land Survey T 8N R 6W L-11  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

STATE OF MICHIGAN  
 IONIA COUNTY  
 RECEIVED FOR RECORD

10 OCT 95 4:07 P.M.

DIANE M. ADAMS  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARINUS MULDER, in a field survey on March 22, 1995  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 This corner was first set by U.S. Deputy Surveyor, Orange Risdon in 1831. A wood post was set witnessed by a 15" White Oak S 60° W 32 links and a 15" White Oak N 60° E 27 links.  
 PERPETUATION: D.C. Crawford former Ionia County Surveyor performed a sectional survey in Section 25, July 1888 recorded in Volume 1, page 440 of the Ionia County records. Crawford shows no witnesses for L-11.  
 No other information is recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 The position of this corner is at the end of Schaefer Road. Excavated area opposite North-South 1/4 line fence but found no substantial evidence. Set L-11 on line with the Southeast and Southwest section corners and opposite the North-South 1/4 line fence. Distances to the West and East measure good.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36 steel rod with a 2 3/4" diameter cap stamped "Ionia County - P.S. 25863" witnessed by:  
 Centerline 4" steel post North 20.50 feet  
 Nail & Tag North side 5" Elm N 78° W 10.20 feet  
 Nail & tag Northwest side 6" Oak S 45° E 2.64 feet  
 Nail & tag top of 24" Oak stump S 20° E 38.66 feet

Ratified by Peer Group  
 P.A. 345 Ionia County

Date 9-27-95  
 Marinus A. Mulder, Chairman

Signed by Marinus A. Mulder Date OCTOBER 2, 1995