

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>8</u> N. <u>X</u> , R. <u>8</u> <u>X</u> . W.		I-1, J-1, K-1
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. _____, R. _____ E. _____ W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. _____, R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Gary C. Bilow, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 19, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

No Record Since G.L.O. Survey

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-1 Set 4" x 36" Concrete Monument - Set on Township Line G.L.O. Dist from SW Cor Section 35 T9N R8W
- J-1 Set 4" x 36" Concrete Monument - 1/2 Way and On Line Between I-1 and K-1
- K-1 Found 1" Iron Pipe from Ionia County Road Commission Witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Set 4" x 36" Concrete Monument 3' S. of N. Edge Bricker Rd. 0.5' Below Rd Surface N45°E 26.32' 4" Oak Spike & DNR Tag N15°E 17.62' 7" Oak Spike & Tag #19003 N87°W 33.00' SW Cor Sec 35 T9N R8W Capped 1/2" Re-Rod S41°W 34.27' 15" Oak Spike & DNR Tag	J-1 Set 4" x 36" Concrete Monument 4' S. of S. Edge Bricker Rd. West 44.59' 10" Basswood Spike & DNR Tag N26°W 35.49' 26" Oak Spike & DNR Tag S72°E 18.32' 8" Oak Spike & DNR Tag N42°E 46.22' 25" Oak Spike & DNR Tag	K-1 Found 1" Iron Pipe 3' W. of Centerline Berridge Rd. & 5' N. of Centerline Bricker Rd. @ Rd. Surface S69°E 38.49' 14" Oak Spike & Tag #19003 N02°W 44.67' 12" Oak Spike & Tag #19003 S11°E 50.52' 12" Oak Spike & DNR Tag N76°W 58.13' 24" Stump Spike & Tag #19003
---	---	--

SIGNED BY _____ DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. 26453 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____