

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ionia</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>8N</u> R <u>8W</u>	<u>K-3, K-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald L. Bissell, in a field survey on December, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 SW corner Sec. 1	K-2 W 1/4 corner 1" solid iron
Found "T" iron in marsh	from road commission witness
West - 16.30'-10" Oak	
SW - 13.02'-13" Oak	
SE - 17.75'-14" Elm (stump)	
East - 10.65'-12" Wlm (stump)	
NE - 20.67'-15" Elm (stump)	
witness from road commission	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 SW corner Section 1	K-2 W 1/4 corner
"T" iron	1" solid iron with concrete guard post
N88°W - 16.78'-12" W. Oak	N18°W - 42.90'-12" Twin Oak
S52°W - 13.56'-14" W. Oak	N25°E - 78.63'-16" Oak
N51°W - 53.17'-14" B. Oak	N62°E - 65.72'-10" W. Ash
N32°W - 47.82'-20" W. Oak	S67°W - 24.25'-Wood post West of drive

Signed by Donald L. Bissell
 Surveyor's Michigan License No. 18655

Date _____

