

**REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iosco Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T21N R7E E-1  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

3 DEC 97 11:48 A.M.

DONITA M. COYLE  
REGISTER OF DEEDS

**97-48**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James H. Granger, in a field survey on August 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1843 GLO James Mullett Set wood post  
12" B. Ash S67°E 31LKS  
12" Maple S33°W 22LKS  
13LKS W. of SE Cor Sec. 32 T22N R7E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found large spike. Marker is 8.25 ft West of SE cor Sec 32, T22N, R7E as compared to 8.58 ft by GLO.  
Accepted position as previously established.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 9-16-97


*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" Rebar with Remon Cap in Mon Box

Utility Pole S38°W 43.70' nail & tag 16041  
12" Box Elder S16°W 71.92' nail & tag 16041  
Utility Pole S64°E 58.49' nail & tag 16041  
18" Maple N70°E 107.89' nail & tag 16041

E-13 Remon Cap in Mon. Box East 8.25' (T22N, R7E)



Signed by James H. Granger  
Surveyor's Michigan License No. 16041

Date Nov. 10, 1997

**SURVEY &  
REMONUMENTATION**

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975

REVISED JAN., 1983  
REVISED OCT., 1995

MAR 18 1998

SECTION