

FEB 15 2001

SECTION

IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

010 2001

For corners in

IOSCO
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>22N</u> R <u>5E</u>	I - 13
	T <u>21N</u> R <u>5E</u>	I - 1 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
IOSCO COUNTY
FILED

13 FEB 2001 9:21:24 AM

BONITA H. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg, P.S., in a field survey on October 12 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 1844 +/-, GLO Survey, set post, 8" Tamarack, N40E 14 lks, 7" Cedar, N33W 41 lks
 1950+/-, MDOT Highway Maps
 1976 James Campbell, Set 1" Bolt in Mon Box, Liber 248, Page 262
 1988 Northeast Land Surveys, Found 3/4" Bar in Mon Box, Liber 378, Page 496

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 3/4" bar in Mon Box as evidenced by maps and surveys, witnesses check.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-11-2000

James H. Chandler

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Left 3/4" bar in Mon Box and topped with Remon Cap.
 Wcst 3.0' centerline Highway M-55
 N20E - 87.95' 10" Elm
 N80E - 46.32' 8" Elm
 S40E - 49.27' 6" Elm
 S55W - 116.50' Power Pole



Signed by William J. Rigg
Surveyor's Michigan License No. #41108

Date December 22, 2000