

**SURVEY &  
REMONUMENTATION**

FEB 16 1999

REMONUMENTATION CORNER

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED  
**98-28**  
DEC 98 1:12 P.M.

RONITA M. COYLE  
REGISTER OF DEEDS

For corners in

IOSCO <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>21NR 6E</u>	<u>F-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JAMES H. GRANGER, in a field survey on SEPTEMBER 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

No Original corner set.

1972 - Survey & LCRC Jerry Wilcox #14102 Fd.. wood Hub - Set 3/4" pipe  
L217, pg 361 Set 3 witnesses L72, p14

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 9-22-98

*James H. Granger*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Field measure to position identified by Wilcox notes on 1972 survey. The hub found appears like all the hubs Wilcox used during their traverse work. Also evaluated against prorated measurement to NW cor. Sec. 6 and searched for hub at approx. NW cor. Sec. 4 Nothing found 3/4" Iron set by Wilcox does not fit with prorated measurements on both sides of Township line. Establish cor. position midway and on-line between NE and NW sec. corners which lie 32.55' west of 3/4" pipe location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x24" iron rod w/ remon cap

3/4" Iron pipe	EAST	32.55'	
Triple Maple 36"	N80°E	19.22'	nail & tag
Ash 18" dia.	S7°E	19.32'	nail & tag
Ash 16" dia.	S59°W	13.79'	nail & tag



Signed by James H. Granger  
Surveyor's Michigan License No. 16041

Date November 2, 1998