

**IOSCO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

042 2000

Iosco Co. _____ Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 21NR 6E
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

G-7
**SURVEY &
REMONUMENTATION**
FEB 15 2001
SECTION

STATE OF MICHIGAN
IOSCO COUNTY
FILED
30 NOV 2000 2:10:31 PM
BONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, JAMES H. GRANGER, in a field survey on July, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 GLO Set Wood Post
John Mullett 10" B. Ash N06°E 24 lks
J.H. Munro 14" B. Ash S08°E 18 lks

1989 Neil B. Livasy 31611

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found existing corner of record 1/2 inch iron in mon. box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" x 30" rebar w/Rerron Cap in mon. box
PP N45°E 40.19' nail & tag 16041
11" S. Pine N41°W 64.25' nail & tag 16041
Corner fence post S05°E 43.11' nail & tag 16041
4" S. Pine S32°E 47.99' nail & tag 16041

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON OCT 11 - 2000

James H. Granger



Signed by James H. Granger
Surveyor's Michigan License No. 16041

Date NOV. 29, 2000