

SURVEY & REMONUMENTATION

FEB 16 1999

REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98-30

For corners in

<u>IOSCO</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21NR 6E</u>	<u>H-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
IOSCO COUNTY
FILED

8 DEC 98 1:13 P.M.

BONITA H. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JAMES H. GRANGER, in a field survey on SEPTEMBER 29, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


No original corner set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: James H. Granger

Field measured from NE cor. Sec. 3 to NW cor. Sec. 6. Found nail in approx. location of corner. Evaluated measurements on both sides of Township line. Established cor. location midway and online between NE and NW sec. corners at 2,615.07' west of NE corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x24" iron rod w/ remon cap
- Maple 6" dia. N50°W 63.99' nail & tag
- Maple 24" dia. N20°E 87.03' nail & flag
- Maple 5" dia. S50°E 35.25' nail & tag
- Aspen 16" dia. S20°W 38.36' nail & tag
- 2" Iron pipe S15°W 28.13'



Signed by James H. Granger
Surveyor's Michigan License No. 16041

Date November 2, 1998