

**SURVEY & REMONUMENTATION**

FEB 16 1999

**REMONUMENTATION CORNER**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

98-34

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

8 DEC 98 1:13 P.M.

DONITA M. COYLE  
REGISTER OF DEEDS

For corners in

IOSCO	Located In:	Corner Code #
(County)		
1. Public Land Survey	T21N R6E	K-1
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**Register of Deeds Stamp & File Number**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, JAMES H. GRANGER, in a field survey on SEPTEMBER 29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1843 GLO John Mullett Set wood post 10" W BIRCH S27°W 25 LKS  
12" HEMLOCK S48°E 27 LKS  
SW COR. SEC. 36 T22N, R6E 36 LKS

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


Field measured to approx location based on single proportionate measurement between NE cor. Sec. 1 and NW cor. Sec. 2. No original evidence found. Found ex. fence approx. 7.6' East of calc. position. Evaluated measurements on N. side of Township line to establish consistency with measured vs. recorded distances. Established cor. Location at 5,191.93 West of NE cor. of sec. 1 on line between NE cor. Sec. 1 and NW cor. Sec. 2

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" x 24" iron rod w/ remon cap

Aspen 6" dia.	N80°W	45.79'	nail and tag
W. Birch 4" dia.	N45°E	13.38'	nail and tag
Maple 12" dia.	S15°E	16.42'	nail and tag
Aspen 14" dia.	S40°W	19.12'	nail and tag
SW cor. Sec.36	West	15.91'	remon cap T22N, R6E

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-22-98  
*James H. Granger*



Signed by *James H. Granger*  
Surveyor's Michigan License No. 16041

November 2, 1998