

FEB 16 1999

SECTION

IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

98-47

For corners in

<u>Iosco</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22</u> R <u>5E</u>	<u>T-1</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

8 DEC 98 1:19 P.M.

BONITA M. COYLE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William J. Rigg, in a field survey on Oct. 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1844 GLO Survey Set Post  
12" Beach S52E 21 lks.  
10" Maple S31W 28 lks.

1950 MDOT Highway Maps  
Reference Corner from centerline of Highway M-65

1991 LCRC by Keyno J. Shellenbarger #30101  
Fnd. RR Spk. LCRC 91-9

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Survey by Keyno J. Shellenbarger #30101  
References Corner Liber 468, Pages 472-474

Found RR spike per LCRC & Survey by Keyno J. Shellenbarger

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
74 OF 1970 AT A MEETING  
HELD ON 9-22-98

*James H. Branger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998 Remonumentation by William J. Rigg #41108

Fnd RR Spk. and Replaced it with a 5/8" Rebar with Remon Cap.

S45E 65.80' Power Pole  
West 64.47' PK in Centerline Highway M-65  
N70E 110.09' Fence Post  
N05W 201.15' Fence Post



Signed by William J. Rigg  
Surveyor's Michigan License No. 41108

Date Nov. 10, 1998