

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

013 2000

For corners in

IOSCO
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>22N</u> R <u>5E</u> | <u>I-2</u> |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |

STATE OF MICHIGAN
IOSCO COUNTY
FILED
13-2000
3 JAN 0 4:05 P.M.

SARITA H. COPEL
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg, in a field survey on August, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3	•	2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1844 +/- GLO Survey 10" Beech N81W 18 lks, 12" Maple S80E 24 lks
- 1950 +/- MDOT Highway Maps
- 1989 Found 1" Rod by Northeast Surveys
- 1994, 1997 Found and accepted RR spike by Keyno Shellenbarger

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR spike as held in previous surveys and LCRC.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-13-99

James H. Shangan

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted position of RR spike and replaced with a 5/8" rebar with Remon Cap.

- East 57.60' Face of concrete R/W marker
- West 59.13' Face of concrete R/W marker
- N25E 199.42' Tag in power pole #30101
- S30E 154.83' Tag in power pole #30101

Signed by William J. Rigg P.S.
Surveyor's Michigan License No. 41108

Date DEC. 27, 99