

**IOSCO COUNTY REMONUMENTATION CORNER**

LAND SURVEY RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

**002 2000**

For corners in

IOSCO  
(County)

Located In: Corner Code #

1. Public Land Survey

T22N R 5E I-3

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

3 JAN 0 3:42 P.M.

2-2000

BONITA K. FOLEY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, William J. Rigg, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3									•				
4	7		8		9		10		11				12
5													
6	18		17		16		15		14				13
7													
8	19		20		21		22		23				24
9													
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1844 +/- GLO Survey 10" W. Pine N82W, 20" W. Pine S37W
- 1950 +/- MDOT Highway Maps
- 1973 Found 1" pipe by James Campbell
- 1989 Found pipe w/cap by Northeast Surveys

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe, position agrees with previous surveys and Highway Maps.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 10-13-99

*James H. Shanger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted position of 1" pipe and replaced with a 5/8" rebar with Remon Cap.

- S45E 73.85' Power Pole
- N75E 152.55' Fence Post
- N40W 139.15' Fence Post on North end of gate
- S80W 92.40' Fence Post



Signed by William J. Rigg P.S.  
Surveyor's Michigan License No. 41108

Date Dec 27, 99

APR 27 2000

SECTION