

IOSCO COUNTY REMONUMENTATION CORNER

LAND CORNER RE-ESTABLISHMENT CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

007 2000

For corners in

IOSCO
 (County)

Located in:

Corner Code #

1. Public Land Survey

T22N R SE I-5

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

STATE OF MICHIGAN
 DEEDS DIVISION
 LANSING
 7-2000
 3 JAN 0 4:04 P.M.

SMITH R. DAVIS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William J. Riss, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1844 +/- GLO Survey
 10" Beech N82W .03 lks
 10" Beech S60E .63 lks
- 1950 +/- MDOT Highway Maps
- 1977 Found Bolt Spike by Keyno Shollenbarger #30101

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Bolt spike as held in previous LCRC and Highway Maps.


ACCEPTED BY THE IOSCO COUNTY
 SURVEY PEER GROUP AS THE
 OFFICIAL CORNER UNDER P.A.
 245 OF 1980 AT A MEETING
 HELD ON 10-13-99

James H. Stranger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted position of Bolt spike and replaced with a 5/8" rebar with Reunou Cap.

- S45E 96.13' Power Pole
- West 56.82' Highway R/W iron
- S30W 83.79' Fence Post
- N35W 62.22' Fence Post



Signed by William J. Riss
 Surveyor's Michigan License No. 41108

Date Dec 27, 99

2000

SECTION