

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

008 2000

For corners in

IOSCO
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>22</u> R <u>5E</u> | <u>I-6</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling
in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

STATE OF MICHIGAN
IOSCO COUNTY
FILED
6-2000
3 JAN 0 4:04 P.M.

MONTA N. DYLL
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5			4		3		2		1
3													
4		7		8			9		10		11		12
5													
6		18		17			16		15	●	14		13
7													
8		19		20			21		22		23		24
9													
10		30		29			28		27		26		25
11													
12		31		32			33		34		35		36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1844 +/- GLO Survey
 - 10" Beech N82W .03 lks
 - 10" Beech S60E .63 lks
- 1950 +/- MDOT Highway Maps
- 1997 Survey and L.C.R.C. by Herbert J.Kobs, Found and accepted Bolt Spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Bolt spike as held in previous LCRC, Survey and Highway Maps.


ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-13-99

James H. Krueger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted Bolt spike and replaced with a 5/8" rebar with Remon Cap.

- West 76.70' 10" Twin Elm
- East 75.47' Fence Post
- S50E 60.72' Fence Post
- N45W 82.64' Fence Post



Signed by *William J. Rigg*
Surveyor's Michigan License No. 41108

Date Dec 27, 99

2000

SECTION