

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

IOSCO
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>22N</u> R <u>5E</u> | <u>I-7</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

010 2000

STATE OF MICHIGAN
IOSCO COUNTY
FILED
10-2000
3 JAN 0 4:05 P.M.

RONITA M. DYBLE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		14		15		16		17		18		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1844 +/- GLO Survey 12" Beech N34E 5 lks, 8" Beech S65W 18 lks
- 1950 +/- MDOT Highway Maps show corner
- 1973 LCRC by Richard Miller references corner.
- 1997 Survey and LCRC by Herbert Kobs found and held Bolt spk. In Mon Box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found and held bolt spk. per previous surveys by Richard Miller and Herbert Kobs.


ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-13-99

James A. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted position of bolt spk. and replaced with 5/8" rebar and remonumentation cap.

- N45E 103.75' Power Pole
- S45E 113.0' Power Pole
- N30E 69.85' Top center of concrete culvert end
- N49W 83.6' Top center of concrete culvert end



Signed by William J. Rigg
Surveyor's Michigan License No. 41108

Date Dec. 27, 1999

SECTION