

**SURVEY &
REMONUMENTATION**

FEB 15 2001

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

IOSCO

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------|
| 1. Public Land Survey | T <u>22N</u> R <u>5E</u> | I-8 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

008 2001

STATE OF MICHIGAN
IOSCO COUNTY
FILED

13 FEB 2001 9:21:24 AM

BONITA N. COYLE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1. **William J. Rigg, P.S.**, in a field survey on October 12 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22	●	23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 1844 +/-, GLO Survey, set post, 24" W. Pine, S40W 28 lks, 10" W. Pine, N26E 32 lks
 1973 Richard L. Miller, References corner in survey, Liber 229, Page 821
 1973 Richard Miller, Found 1/2" Rod, See LCRC 77-11
 1977 Richard Miller, Set 3/8" Rod, See LCRC 83-4
 1999 William Rigg, References corner in survey, Liber 590, Page 228
 1999 William Rigg, References corner in survey, Liber 580, Page 261

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/8" rod as evidenced, witnesses check.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-11-2000

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replaced 3/8" rod with 5/8" bar and remon cap
- N30E - stop sign - 27.9'
- S35E - stop sign - 42.6'
- West - C/L Hwy M-65 - 32.1'
- West - survey cor. - 92.15'



Signed by William J. Rigg
Surveyor's Michigan License No. #41108

Date December 22, 2000