

FEB 15 2001

IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

IOSCO (County)	Located In:	Corner Code #
1. Public Land Survey	T22N R 5E	1-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

007 2001

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

13 FEB 2001 9:21:24 AM

BONITA M. COYLE  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William J. Rigg, P.S., in a field survey on October 12 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1844 +/-, GLO Survey, set post, 8" Beech, S42E .30 lks, 6" Sugar, N27W .08 lks  
1950 +/- MDOT Highway Maps  
1973 Richard L. Miller, Found mon box at intersection, See LCRC 83-04  
1979 Richard Miller, References corner in survey, Liber 282, Page 339  
1990 Philip D. Case, Found 1/2" rod in mon box, Liber 400, Pages 308-310  
1996 James H. Granger, References corner in survey, Liber 499, Page 459  
1999 Joseph S. Curtis, Set 1/2" Rerod in mon box, See LCRC 99-01

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod in mon box as evidenced, witnesses check.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
845 OF 1990 AT A MEETING  
HELD ON 10-11-2000

*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" rod with 5/8" bar and remon cap  
Mon box C/L Int of Hwy M-65 & Hwy M-55  
S65W 134.79' top of Highway Marker Post  
S65E 180.51' top of Highway Marker Post  
N25E 194.57' top of Highway Marker Post  
S40W 188.55' 1/2" witness iron



Signed by William J. Rigg  
Surveyor's Michigan License No. #41108

Date December 22, 2000