

FEB 15 2001

SECTION

IOSCO COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

IOSCO (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>5E</u>	<u>L-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

018 2001

STATE OF MICHIGAN
IOSCO COUNTY
FILED

13 FEB 2001 9:21:24 AM

BONITA M. COYLE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg, P.S., in a field survey on October 12, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1844 +/-, GLO Survey, set post
 - 1973 Edmands Engineering, References corner in survey, Liber 236, Page 379
 - 1973 Edmands Engineering, References corner in survey, Liber 229, page 726
 - 1980 Richard L. Miller, Found PK nail, Liber 282, Page 341
 - 1990 Corey Huglius, Found PK nail, Liber 395, Page 777
 - 1990 Philip D. Case, References corner in survey, Liber 400, Pages 308-310

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-11-2000

James H. Grayson

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no evidence of PK nail, but all witnesses are in good condition, re-established corner from witnesses and verified distances shown on surveys to section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Drilled PK nail into bridge deck.
- Centerline of M-65, 9.5 ft. East
- NW End Steel Post 64.95'
- NE End Steel Post 69.23'
- SE End Steel Post 70.51'
- SW End Steel Post 66.95'



Signed by William J. Rigg, P.S.
Surveyor's Michigan License No. #41108

Date December 22, 2000