

**SURVEY & REMONUMENTATION**

**FEB 15 2001**

**SECTION**

**IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**010 2001**

For corners in

IOSCO

(County)

Located In:

Corner Code #

1. Public Land Survey

T 22N R 5E I-13

T 21N R 5E I-1

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

13 FEB 2001 9:21:24 AM

RONITA M. COYLE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, **William J. Rigg, P.S.**, in a field survey on **October 12 2000** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
 1844 +/-, GLO Survey, set post, 8" Tamarack, N40E 14 lks, 7" Cedar, N33W 41 lks  
 1950+/-, MDOT Highway Maps  
 1976 James Campbell, Set 1" Bolt in Mon Box, Liber 248, Page 262  
 1988 Northeast Land Surveys, Found 3/4" Bar in Mon Box, Liber 378, Page 496

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 3/4" bar in Mon Box as evidenced by maps and surveys, witnesses check.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 10-11-2000

*James H. Stranger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Left 3/4" bar in Mon Box and topped with Remon Cap.
- West 3.0' centerline Highway M-55
- N20E - 87.95' 10" Elm
- N80E - 46.32' 8" Elm
- S40E - 49.27' 6" Elm
- S55W - 116.50' Power Pole



Signed by *William J. Rigg*  
Surveyor's Michigan License No. #41108

Date December 22, 2000