

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

IOSCO
(County)

Located In:

Corner Code #

1. Public Land Survey

T22NR 5E

J-3

T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling
In Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

012 2000

STATE OF MICHIGAN
IOSCO COUNTY

FILED
12-2000
3 JAN 0 4:05 P.M.

BRITA H. OWIE
Register of Deeds, Stamp & File Number

I, William J. Rigg, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1844 +/- GLO Survey 8" Beech North 51 lks, 10" Hemlock S10W 48 lks
- 1973 Found 1" pipe by James Campbell
- 1977 Found 1/2" rod by Richard Miller
- 1989 Found 1" pipe by Northeast Surveys
- 1990 Found 1/2" rerod by Keyno Shellenbarger

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar in the position as shown in previous survey and LCRC's.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
74 OF 1970 AT A MEETING
HELD ON 10-13-99

James H. Branger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted position of 1/2" Rebar and replaced with a 5/8" rebar with Remon Cap.

- South 34.42' Fence Post
- North 25.75' Fence Corner Post
- S75E 105.68' NW Face Telephone Post
- N45W 36.05' Fence Post



Signed by William J. Rigg
Surveyor's Michigan License No. 41108

Date DEC. 27, 99