

IOSCO COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

IOSCO

(County)

Located in:

Corner Code #

1. Public Land Survey

T22N R SE

J-5

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___

T ___ R ___

S ___

T ___ R ___

3. Miscellaneous Property in Sec.

S ___

T ___ R ___

S ___

T ___ R ___

001 2000

STATE OF MICHIGAN
IOSCO COUNTY

FILED

1-2000

3 JAN 0 3:42 P.M.

DONITA W. DYBLE

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, William J Rigg, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1844 +/- GLO Survey 10" Beech N82W .03 lks, 10" Beech S60E .63 lks

1977 Richard Miller set 1/2" rod

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-13-99

James H. Shanger


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar per LCRC 77-9, Position agrees with computed position from Survey by Herbert J. Kobs, Liber 535, Pages 900-901. Position falls 41.91 feet West of proportionate distance between I5 and K5, but falls on true line between I5 and K5. Position also agrees with established fence lines North and South and 1/2" rebar 33 ft. North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted position of 1/2" Rebar and replaced with a 5/8" rebar with Remon Cap.

N 40° W 45.50 ft. 4" Pine
North 41.31 ft. Fence Corner Post
South 21.0 ft. Fence Corner Post
S 20° E 23.65 ft. Fence Post
Approximately 5 ft. South of Road Centerline



Signed by William J Rigg
Surveyor's Michigan License No. 41108

Date Dec 27, 99

APR 27 2000

SECTION