

**IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

005 2000

For corners in IOSCO (County) Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T22N R SE I-7  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_

2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED  
5-2000  
3 JAN 0 4:04 P.M.  
  
DORITA H. COBLE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William J. Riss, in a field survey on August, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		35		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1844 +/- GLO Survey  
 12" Beech N34E .05 lks  
 8" Beech S65W 18 lks
- 1974 Survey by Richard Miller references corner.
- 1996 Survey and LCRC by James Grautger show setting 5/8" rebar
- 1997 Survey by Herbert Kobs shows holding 5/8" rebar.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" Rebar per previous surveyors.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-13-99  
*James H. Grautger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Accepted position of 5/8" rebar and placed remonumentation cap.
- N65W 57.61' 4" Box Alder
- S20W 35.55' 6" Box Alder
- South 32.07' Fence Corner
- North 32.29' Fence Post



Signed by William J. Riss  
 Surveyor's Michigan License No. 41108

Date Dec 27, 99

SECTION