

**IOSCO COUNTY REMONUMENTATION CORNER**

**LAND CORNER REINFORCEMENT CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**009 2000**

For corners in

IOSCO

(County)

Located in:

Corner Code #

1. Public Land Survey

T22N R SE

K-2

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William J. Rigg, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1844 +/- GLO Survey, set post 24" W, Pine S2W 1.21 lks, 6" Beech N12E 16 lks

1973/4 Survey and LCRC by James Campbell. 1" Pipe and 1/2" pipe

1997 LCRC by Keyno Shellenbarger. Found 1/2" rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod per previous surveyors at approximate proportionate distance between K1 and K3.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-13-99

*James H. Shellenbarger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Accepted position of 1/2" rod and replaced with 5/8" rebar and remonumentation cap.

West 28.28' Fence Post

N45W 44.06' Fence Post

N65E 33.17' Fence Post

S30E 161.41' Center of West bolt in NW corner of Electrical Tower 7' above ground.



Signed by William J. Rigg  
 Surveyor's Michigan License No. 41108

Date Dec 27, 1999

SECTION