

FEB 16 1999

SECTION

IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

IOSCO (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 5E	K-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
IOSCO COUNTY
FILED

8 DEC 98 1:14 P.M.

BONITA H. COYLE
REGISTER OF DEEDS

98-37

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg in a field survey on Oct 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1844+/- GLO Survey
14" Hemlock S9W 20 lks.
12" Elm N37E 13 lks.

1974 LCRC & Survey by James G. Campbell

1977 1/2" Bar by Richard L. Miller

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found and held 1/2" pipe as re-established by James G. Campbell, #15397 in Liber 74-293 and as accepted by Richard L Miller in LCRC 77-9.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 9-22-98


James H. Krueger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998 Remonumentation by William J. Rigg, #41108

Fnd 1/2" bar and replaced with 5/8" rebar with Remon Cap.

N45W 77.70' Maple Clump
S50E 69.68' Power Pole
East 30.30' Fence Corner
S30E 52.20' Power Pole



Signed by *William J. Rigg*
Surveyor's Michigan License No. #41108

Date Nov. 10, 1998